Bruhat Bangalore Mahanagara Palike
Excecutive Engineer Project Division Yelahanaka

Name of Work: Modified Estimate for Improvements of roads and drains at Chokkanahalli surrounding area in Ward No.05 (Jakkur) Byatarayanapura Sub division

Modified Schedule - B

Sl No	Description of Item	Unit	Quantity	Rate, Rs	
				In Figures	In Words
1	KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications(P.No-143 &136 ,I No-19.1&17.4& 17.1,KPWD SR 2018-19) 8km lead= 57+2.0x1.28x8 = 77.48	Cum	3113.27	226.00	Rupees Two Hundred Twenty Six Only
2	KSRRB M2100-10. Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs. with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. (P.No-222,I No-27.18,KPWD SR 2018-19)	Cum	394.19	5691.78	Rupees Five Thousand Six Hundred Ninety One And Paise Seventy Eight Only
3	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specifications. Specificatio (I No-28.8.2,P No-229,KPWD SR 2018-19)	Tn	46.67	75927.20	Rupees Seventy Five Thousand Nine Hundred Twenty Seven And Paise Twenty Only
4	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2200. including cost of materials, labour, HOM complete as per specificationsdo- Wall & bottom thickness 15cm (I No-37.59.2,P No-271,KPWD SR 2018-19)	Cum	756.63	7422.13	Rupees Seven Thousand Four Hundred Twenty Two And Paise Thirteen Only

Scanned by TapScanner

ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

Bruhat Bangalore Mahanagara Palike

providing and fixing pre cast covering slab made out of CC with 10cm thick and finishing cutting ,including form curing,including cost of alll materials, labour,hire charges of machinery,loading,unloading,lead and transportation etc ,copmplete. (Data Rate)	Sqm	2002.88	2453.33	Rupees Two Thousand Four Hundred Fifty Three And Paise Thirty Three Only
Providing and fixing pre cast covering slab 250mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.As per Engineer incharge ,KPWD SR 2018-19	Sqm	27.00	5687.69	Rupees Five Thousand Six Hundred Eighty Seven And Paise Sixty Nine Only
Above 125%	Sqm	76.32	5418.00	Rupees Five Thousand Four Hundred Eighteen Only

Executive Engineer,
Yelahanka Division,
BBMP Bangalore

Scanned by TapScanner